Loss Solutions Group, LLC
Toll Free 866.899.8756
Fax 860.639.5158
www.LossSolutionsGroup.com

October 3, 2025

Mr. Tom Laufer
Hanover Insurance
440 Lincoln Street
Worcester, MA 01615

RE:	Insured:	John Kwasneski
	Claim Number:	85-00721214
	LSG Matter Number:	426600.4046-00
	Date of Loss:	January 2, 2025

Dear Mr. Laufer,

Thank you for choosing Loss Solutions Group as your equipment loss consultant. This report serves to provide an analysis of the above-referenced claim.

Assignment:

Loss Solutions Group was contacted by Mr. Tom Laufer of Hanover Insurance. The scope of this assignment was to address the extent of damage, salvage value, and repair / replacement costs associated with the insured's damaged two (2) ton HVAC system and ducting reportedly related to a smoke / soot event on January 2, 2025.

Findings and Analysis:

Loss Solutions Group contacted the insured, Mr. John Kwasneski (724-935-5005), to advise him of our involvement in reviewing this claimed event. During our conversation, Mr. Kwasneski reported that on January 2, 2025, a fire broke out in his three (3)-story, two (2) bedroom, one (1) bath townhome (1,088 SQFT) located at 607 Westchester Drive in Wexford, Pennsylvania, causing significant damage. He noted that the ceilings and walls were severely affected, with drywall peeling and falling away due to the intensity of the fire. As it occurred mid-winter, it was reported that the furnace was running, causing soot and smoke to circulate throughout the apartment, penetrating the ductwork. Installed in 1981 when the building was constructed, the non-insulated foil ductwork was either burnt, melted, or contaminated with smoke and soot, necessitating a cleanout. Given its age, condition, and exposure to excessive heat, the ductwork is deemed unreliable for cleaning and requires replacement, including plenums, and other HVAC related items.

© 2022 by Loss Solutions Group, LLC. All rights reserved.

Vendor Contact

Loss Solutions Group contacted the insured's HVAC vendor, Restano Heating, Cooling, & Plumbing (724-327-7137), and spoke with Ms. "Jennifer" in the front office to discuss the claimed event, identified damages, and to obtain more details on the proposed replacement. Ms. "Jennifer" initially required authorization from the homeowner before proceeding, which was obtained. However, even with permission, Restano declined to provide a detailed breakdown of the job, including required equipment or specifics on the proposed replacement. Due to this lack of information, Loss Solutions Group performed an independent estimate for a typical two (2) bedroom, one (1) bath, three (3)-story townhome (1,088 SQFT) replacement job that aligns with the cost range presented.

Scope of Damage

Loss Solutions Group submits that the insured reportedly sustained significant damage to their two (2) ton HVAC system and ducting reportedly related to a smoke / soot event on January 2, 2025.

Age & Condition

The insured reported that the townhome was built in 1981, making the affected equipment around forty-four (44) years old and in average condition at the time of the claimed event.

Reparability

Loss Solutions Group has reviewed the provided information, and we have discussed the damage with the insured. We submit that the proposed replacement path is warranted due to the extent of damage reportedly sustained during the claimed event.

Cost Analysis

Loss Solutions Group has researched the costs using alternate vendor resources, historical references, similar equipment costs, and vendor experience. The following is a breakdown of the associated costs for a two (2) bedroom, one (1) bath (1,088 SQFT) townhome HVAC replacement.

RESTANO HEATING, COOLING, & PLUMBING (724-327-7137) ESTIMATE # 63208415

Loss Solutions Group has reviewed the amount of $21,890.00 for the replacement of the insured's HVAC equipment and ducting.

Absent a breakdown or supporting information from the HVAC vendor, Loss Solutions Group performed an independent cost analysis. Included in the cost is an amount for a basic 80% single stage gas furnace, a two (2) ton single stage air conditioner condensing unit, a two (2) ton matching vertical evaporator coil, a basic WIFI enabled programmable thermostat, roughly fifty feet (50') of copper tubing to run from the condenser outside to the first floor evaporator unit, miscellaneous electrical components, miscellaneous other equipment, insulated ducting runs, new grills and

© 2022 by Loss Solutions Group, LLC. All rights reserved.

returns, trunk ducting, two (2) new ducting plenums, and miscellaneous other ducting supplies.. We submit these components are required to complete the replacement and the costs are fair and reasonable.

Loss Solutions Group estimated the labor costs for the vendor to diagnose the damage and to perform the repairs as well as the travel expenses and permitting fees. We submit that these amounts are fair and reasonable to complete the scope of work as presented to us.

Note: A difference was noted between the claim cost and Loss Solutions Group's researched cost totaling $1,460.00. The difference is attributed to two (2) items not assumed to be part of the pre-loss HVAC system: an electrical surge protector and an air cleaning unit, both considered add-ons. Should the vendor agree to provide additional information supporting these items' pre-loss existence, we can amend our analysis herein.

RCV

Loss Solutions Group submits an amount of $20,430.00 (RCV) as being fair and reasonable to return the insured to a pre-loss condition. A further breakdown of the pricing is available in the attached spreadsheet.

ACV

Loss Solutions Group submits an actual cash value (ACV) amount of $11,835.00 based on linear age depreciation of the materials only. We estimate the average life expectancy of the equipment to be around twenty (20) years.

Salvage

Loss Solutions Group submits that there is little to no salvage value associated with this claimed event.

Summary:

Loss Solutions Group's findings herein are based upon all information that was available at the time of this writing. The opinions are based upon reviewed documentation, interviews, research, experience, historical references, training and education.

1. The insured, John Kwasneski, claimed that he sustained major damages to his two (2) ton HVAC system and ducting reportedly related to a smoke / soot event.

2. The insured reported that the townhome was built in 1981, making the affected equipment around forty-four (44) year old and in average condition at the time of the claimed event.

© 2022 by Loss Solutions Group, LLC. All rights reserved.

3. Loss Solutions Group has reviewed the provided information, and we have discussed the damage with the insured. We submit that the proposed replacement path is warranted due to the extent of damage reportedly sustained during the claimed event.

4. Loss Solutions Group submits an amount of $20,430.00 (RCV) as being fair and reasonable to return the insured to a pre-loss condition. A further breakdown of the pricing is available in the attached spreadsheet.

    a. A difference was noted between the claim cost and Loss Solutions Group's researched cost totaling $1,460.00. The difference is attributed to two (2) items not assumed to be part of the pre-loss HVAC system: an electrical surge protector and an air cleaning unit, both considered add-ons. Should the vendor agree to provide additional information supporting these items' pre-loss existence, we can amend our analysis herein.

5. Loss Solutions Group submits an ACV amount of $11,835.00 based on linear age depreciation of the materials only.

6. Loss Solutions Group submits that there is little to no salvage value associated with this claimed event.

If you have any questions or if you need any additional information, please feel free to contact Tanner Beuret at (866) 899-8756 ext. 755, or via email at tbeuret@losssolutionsgroup.com. Team Leader Nick Ramos can be reached at (866) 899-8756 ext. 724, or via email at nramos@losssolutionsgroup.com.

Best regards,

Tanner Beuret
Technical Consultant
Loss Solutions Group, LLC

© 2022 by Loss Solutions Group, LLC. All rights reserved.

INSURED: JOHN KWASNESKI
LSG MATTER #: 426600.4046-00
CLAIM #: 85-00721214
DATE OF LOSS: 1/2/2025
CAUSE OF LOSS: SMOKE / SOOT

COLOR DENOTES PRICING DISCREPANCY

RESTANO HEATING, COOLING, & PLUMBING (724-327-7137) ESTIMATE # 63208415													
REF #	ITEM	CLAIM PRESENTED			LSG RESEARCHED RCV			AGE (YEARS)	USEFUL LIFE (YEARS)	ACV (MAX DEPRECIATION 75%)	DEPRECIATION	CONDITION	NOTES
		QTY	UNIT COST	TOTAL	QTY	UNIT COST	TOTAL						
1	HVAC SYSTEM REPLACEMENT	1	$ 21,890.00	$ 21,890.00	0	$ -	$ -	N/A	N/A	$ -	$ -	N/A	VENDOR PRESENTED COST AS LUMP SUM
2	FURNACE	0	$ -	$ -	1	$ 1,650.00	$ 1,650.00	44	20	$ 412.50	$ 1,237.50	AVERAGE	BASIC 80% SINGLE STAGE GAS FURNACE
3	CONDENSER	0	$ -	$ -	1	$ 2,300.00	$ 2,300.00	44	20	$ 575.00	$ 1,725.00	AVERAGE	TWO (2) TON 14.3 SEER SINGLE STAGE AIR CONDITIONER CONDENSING UNIT
4	EVAPORATOR COIL	0	$ -	$ -	1	$ 800.00	$ 800.00	44	20	$ 200.00	$ 600.00	AVERAGE	TWO (2) TON VERTICAL EVAPORATOR COIL
5	THERMOSTAT	0	$ -	$ -	1	$ 150.00	$ 150.00	44	20	$ 37.50	$ 112.50	AVERAGE	BASIC WIFI ENABLED PROGRAMMABLE THERMOSTAT.
6	COPPER	0	$ -	$ -	1	$ 380.00	$ 380.00	44	20	$ 95.00	$ 285.00	AVERAGE	COPPER TUBING TO BE RAN FROM CONDENSER TO EVAPORATOR ROUGHLY FIFTY (50) FEET.
7	ELECTRICAL COMPONENTS	0	$ -	$ -	1	$ 750.00	$ 750.00	44	20	$ 187.50	$ 562.50	AVERAGE	ELECTRICAL DISCONNECT, FUSES, LOW VOLTAGE WIRING FOR THE THERMOSTAT.
8	MISC. MATERIALS FOR EQUIPMENT	0	$ -	$ -	1	$ 750.00	$ 750.00	44	20	$ 187.50	$ 562.50	AVERAGE	TORCH KIT, PVC, CONNECTORS, HARDWARE, FILTER DRIER, REFRIGERANT, ETC.
9	DUCT RUNS	0	$ -	$ -	11	$ 200.00	$ 2,200.00	44	20	$ 550.00	$ 1,650.00	AVERAGE	WE ESTIMATE THAT THE TWO (2) BED, ONE (1) BATH, CONDO HAS ROUGHLY ELEVEN (11) DUCT RUNS IN IT.
10	GRILLS AND RETURNS	0	$ -	$ -	11	$ 50.00	$ 550.00	44	20	$ 137.50	$ 412.50	AVERAGE	WE ESTIMATE THAT THE TWO (2) BED, ONE (1) BATH, CONDO HAS ROUGHLY ELEVEN (11) GRILLS IN IT WITH AT LEAST TWO RETURNS.

© 2022 by Loss Solutions Group, LLC. All rights reserved.

INSURED: JOHN KWASNESKI
LSG MATTER #: 426600.4046-00
CLAIM #: 85-00721214
DATE OF LOSS: 1/2/2025
CAUSE OF LOSS: SMOKE / SOOT

COLOR DENOTES PRICING DISCREPANCY

RESTANO HEATING, COOLING, & PLUMBING (724-327-7137) ESTIMATE # 63208415													
REF #	ITEM	CLAIM PRESENTED			LSG RESEARCHED RCV			AGE (YEARS)	USEFUL LIFE (YEARS)	ACV (MAX DEPRECIATION 75%)	DEPRECIATION	CONDITION	NOTES
		QTY	UNIT COST	TOTAL	QTY	UNIT COST	TOTAL						
11	TRUNK DUCTING	0	$ -	$ -	1	$ 1,000.00	$ 1,000.00	44	20	$ 250.00	$ 750.00	AVERAGE	TRUNK DUCTING TO BE INSTALLED AS OLD DUCTING WAS REPORTEDLY DAMMAGED BEYOND REPAIR.
12	PLENUMS	0	$ -	$ -	2	$ 200.00	$ 400.00	44	20	$ 100.00	$ 300.00	AVERAGE	TWO (2) PLENUMS, ONE SUPPLY AIR AND THE OTHER FOR RETURN AIR.
13	MISC. DUCTING MATERIALS	0	$ -	$ -	1	$ 530.00	$ 530.00	44	20	$ 132.50	$ 397.50	AVERAGE	SLIPS/DRIVES, SEALANT, INSULATION, HARDWARE, ETC.
14	SURGE PROTECTOR	0	$ -	$ -	0	$ 260.00	$ -	N/A	N/A	$ -	$ -	N/A	MATERIALS AND LABOR TO INSTALL SURGE PROTECTOR NOT PART OF PRE-LOSS
15	AIR CLEANER	0	$ -	$ -	0	$ 1,200.00	$ -	N/A	N/A	$ -	$ -	N/A	MATERIALS AND LABOR TO INSTALL AIR CLEANER NOT PART OF PRE-LOSS
16	TRAVEL EXPENSES	0	$ -	$ -	1	$ 400.00	$ 400.00	N/A	N/A	$ 400.00	$ -	N/A	TRIP/FUEL/FREIGHT CHARGES
17	PERMIT FEE	0	$ -	$ -	1	$ 350.00	$ 350.00	N/A	N/A	$ 350.00	$ -	N/A	PERMIT FEES
18	DISPOSAL	0	$ -	$ -	1	$ 300.00	$ 300.00	N/A	N/A	$ 300.00	$ -	N/A	REMOVAL AND DISPOSAL OF THE OLD EQUIPMENT AND DUCTING.

© 2022 by Loss Solutions Group, LLC. All rights reserved.

INSURED: JOHN KWASNESKI
LSG MATTER #: 426600.4046-00
CLAIM #: 85-00721214
DATE OF LOSS: 1/2/2025
CAUSE OF LOSS: SMOKE / SOOT

COLOR DENOTES PRICING DISCREPANCY

RESTANO HEATING, COOLING, & PLUMBING (724-327-7137) ESTIMATE # 63208415														
REF #	ITEM	CLAIM PRESENTED			LSG RESEARCHED RCV			AGE (YEARS)	USEFUL LIFE (YEARS)	ACV (MAX DEPRECIATION 75%)	DEPRECIATION	CONDITION	NOTES
		QTY	UNIT COST	TOTAL	QTY	UNIT COST	TOTAL						
19	LABOR	0	$ -	$ -	72	$ 110.00	$ 7,920.00	N/A	N/A	$ 7,920.00	$ -	N/A	LABOR HOURS FOR ROUGHLY THREE TECHNICIANS FOR THREE FULL DAYS OF WORK.
SUB-TOTAL				**$ 21,890.00**			**$ 20,430.00**			**$ 11,835.00**	**$ 8,595.00**		
SALES TAX				$ -			$ -			$ -	$ -		
TOTAL				**$ 21,890.00**			**$ 20,430.00**			**$ 11,835.00**	**$ 8,595.00**		

TOTAL PRESENTED	**$ 21,890.00**
TOTAL RESEARCHED RCV	**$ 20,430.00**
TOTAL ACV	**$ 11,835.00**
TOTAL DEPRECIATION	**$ 8,595.00**

© 2022 by Loss Solutions Group, LLC. All rights reserved.

Restano Heating, Cooling, & Plumbing
130 Anderson Lane
Pittsburgh, PA 15239

BILL TO
Trident Restoration
607 Westchester Dr
Wexford, PA 15090 USA

ESTIMATE	ESTIMATE DATE
63208415	Jul 02, 2025

JOB ADDRESS
Trident Restoration
607 Westchester Dr
Wexford, PA 15090 USA

Job: 63053449

ESTIMATE DETAILS

Furnace and Air Conditioning Replacement : Replace existing 80 % efficient gas furnace and extinguisher air conditioning system (indoor coil and outdoor condenser,replace flexible ductwork in walls from basement to 1st floor ceiling,install new inside ductwork and flue pipe as needed,tie in gas and electrical,install new digital thermostat,start and test material and labor $ 21,890

Install new plumbing fixtures in 2nd floor bathroom (vanity,toilet,shower and tub combo,install kitchen sink plumbing,install new 40 gallon water heater ,Allegheny County Plumbing permit and inspection ,material and labor $6,800 (plumbing fixtures supplied by others)

SERVICE	DESCRIPTION	QTY	PRICE	TOTAL
1	Our **Basic 2 Ton AC and 80% Gas Furnace** features a single stage condenser and 80% gas furnace. This system is designed to keep you comfortable while being very cost-effective. We include a thermostat to ensure you can maintain the comfort levels in your home. It comes with our exclusive **Basic Warranty** for your peace of mind. Includes: WiFi programmable thermostat Air Cleaner Surge Protector Warranties: 10 Years Compressor and Parts 10 Years Heat Exchanger 2 Year Labor 5 Year No Lemon	1.00	$28,690.00	$28,690.00

POTENTIAL SAVINGS	$0.00
SUB-TOTAL	$28,690.00
TAX	$0.00
TOTAL	$28,690.00

Thank you for choosing Restano Heating, Cooling, & Plumbing. Have a wonderful day!

CUSTOMER AUTHORIZATION

The above prices, specifications and conditions are satisfactory and hereby accepted. Restano Heating, Cooling, & Plumbing is authorized to do work as specified. Payment will be made as outlined.

Sign here Date

TERMS AND CONDITIONS

Change Orders and Substitutions. During the progress of the work under this Agreement, if Customer should order extra work not specified in the Agreement, Contractor may require such extra work to be considered an agreement separate and aside from this Agreement and may require payment for said extra work in advance. Should Contractor be unable to obtain any material(s) specified in the Agreement or any Change Order, Contractor shall have the right at its sole discretion to substitute comparable materials and such substitution shall not affect the Purchase Price.

Warranty. Customer understands that each manufacturer of products may provide factory warranties governing repair and replacement. Customer understands it is Customer's responsibility to refer to each specific manufacturer's warranty guidelines and that it may be necessary for Customer as the owner to register the equipment with the manufacturer and maintain it according to the manufacturer's specifications.

Additional Work. Contractor is not responsible for any drywall, fixtures, structural, or other damage that may occur or be necessary in order to complete the scope of work or any other damage that may occur as a result of the electrical, plumbing, sewer, or HVAC system, or other problems related to the premises. Contractor is not obligated to correct or repair pre-existing structural deficiencies or problems resulting from existing conditions to the property, or the work of others. For example, unless otherwise specified, Contractor is not responsible for any painting, patchwork, or repair work that may be required following any work, nor for any leveling of tubs, shower bases, or floors; repair of damage occurring; correction or repairs to sewer lines, to include, but not limited to, cutting into drywall/concrete, or roof/gutter repairs; correction to landscaping or property damaged in the normal course or operations.

Zoning, Conditions, Permits. Customer agrees to timely furnish all information necessary for Contractor to secure plans and permits for the work called for under this Agreement, and Customer warrants the work as contracted for does not violate any applicable zoning, classification, and building codes. Customer agrees to disclose to Contractor the location of all property lines, underground restrictions or underground utilities, easements or rights of way, pipes, power lines, septic tanks, utility lines, or drain fields that may impact or affect the planned project, and shall indemnify Contractor and hold Contractor harmless from any loss or liability, including attorney fees and costs, resulting from any suits, claims, disputes, losses, or problems related to the above. In the event that the applicable public authority or other government agency subsequently requires modifications or additional labor or materials that were not included in the Agreement, then the Purchase Price may be adjusted. Contractor is not responsible for any special inspections, analysis, or reports that are not ordinarily provided.

Contractor's Right to Cancel. If Contractor determines that this Agreement cannot be performed as intended due, for example, to incorrect pricing, unforeseen structural defects, or conditions to Customer's property, Contractor may cancel this Agreement, notify Customer in writing, and return all monies paid.

Customer's Representations: Customer(s) represents and warrants that (a) Customer(s) owns the premises where the products and services are being provided by Contractor; (b) Customer(s) will provide Contractor with reasonable access to the premises, including access to electrical as may be required by Contractor; and (c) Customer(s) shall be responsible for the preparation, protection, moving, and reinstalling of all items as required by Contractor under this Agreement.

Condensation, Mold and Related Matters. Customer(s) agrees to indemnify and hold Contractor and its employees, agents, and subcontractors harmless from any claims as to the identification, detection, abatement, encapsulation, or removal of mold, asbestos, lead- based products, or other hazardous substances inside or outside of the property at which work is performed. Contractor does not provide mold testing or remediation services.

HVAC, Plumbing, Electrical and Generator Terms & Conditions

Order Structure and Installation. Customer understands that it is Customer's responsibility that certain specifications with regard to existing electrical box and natural gas or liquid propane must be met to install a standby power generation system. Contractor will aid the Customer, but it is Customer's responsibility to contact the local natural gas or liquid propane service provider to confirm the meter and/or tanks are sufficient to handle the new equipment. Contractor will provide assistance in preparing and filing documentation to obtain permits from the appropriate municipalities. Customer understands that it may be necessary to drill a hole into the house foundation for the electrical and gas connections, and Customer will not hold Contractor liable for any damage to the foundation.

Design Conditions. All HVAC equipment is designed by manufacturers according to the standard design temperatures. Contractor is not responsible for cooling/heating beyond standard design temperatures, high humidity levels, system reaching dew point, ductwork sweating/producing condensate due to home infiltration rates, or any other reason. R-values, structural tightness, ductwork conditions, home infiltration, leakage of ductwork, building materials, and any other factor in the load calculation will be determined by the information the Customer provides to Contractor upon initial consultation. Contractor is not responsible for any problems incurred due to incorrect information provided by Customer at the time of consultation and load calculation. If Customer does not authorize Contractor to conduct its own testing to determine load calculations and all insulation values, Contractor shall size the new HVAC system based on the size of the Customer's existing HVAC system. In such case, Contractor shall not be responsible for problems caused by over-sizing (including without limitation short cycling, humidity control, and mold growth) or under-sizing (including without limitation inability to heat or cool within standard design temperatures).

Performance or Condition of Existing Equipment. Contractor is not responsible for the performance, functionality, or compatibility of existing equipment, ductwork, duct board, controls, or other equipment/materials that are not repaired or replaced during a job installation and that Customer agrees to keep in place.

Existing Line Set. Contractor is not responsible for any problems with heating or cooling due to the existing line set, which may require repair and replacement for an additional cost to the Customer in the event Contractor is unable to pull a proper vacuum on an existing line set.

Existing Gas Pipe. Contractor is not responsible for the condition of any existing gas pipe that is not readily accessible. Customer is responsible for any additional costs incurred if pressure testing is required to identify leaks and necessary repairs.

Existing Attic Access Stairs. In the event Customer's existing stairs/attic access cannot be safely utilized for the removal and installation of equipment, an alternate method or access may be required. Contractor is not responsible for (a) the replacement or repair of steps, stairs or panels that must be removed to complete removal or installation work; and/or (b) any property damage resulting from the removal of access steps, stairs, or panels.

Condensate Line. These services do not warranty any condensate or water leaks related to existing plumbing issues, PVC joints that separate, or due to improper slope of condensate lines between cooling coil and plumbing. It is understood and agreed to by Customer that the condensate lines are part of the plumbing system and that over a period of time dirt, sludge, and debris can accumulate in the condensate line. Under no circumstances does the Contractor warranty any part of a building's existing condensate piping and related plumbing; or damages related to existing condensate piping.

Drain Clearing. Should any drain cleaning cable become stuck in the line it is the responsibility of the Customer for removal and/or additional repairs. If a sewage spill occurs, including one deemed hazardous material, the cost of cleanup is the responsibility of the Customer.

Huge Sale on orders over $2,000 | Prices so low we can't advertise! Add to cart for your savings!

HVACDIRECT.COM

Search entire store

SIZING GUIDE SIGN IN

1-888-976-9793 Today's Hours 8am - 11pm est

SHOPPING CART

Cooling | Heating | Ductless Mini Split | Commercial | Air Quality & Filters | Fans & Ventilation | Fireplaces & Outdoor | Water & Plumbing | Electrical & Solar | Parts & Tools

Home > 2 Ton 14" Width Vertical Evaporator Coil - Cased - R32

2 Ton 14" Width Vertical Evaporator Coil - Cased - R32

SAVE $167.00

By Private Brand Model AQ-CAPFA2422A3 ID 197416

In Stock - Ready to Ship

Was $793.00

Your Low Price $626.00

As low as $20.20/mo*

QTY 1 ADD TO CART

26,913 Ratings | Product Specifications | Reviews | Questions and Answers

ACCESSORIES

Huge Sale on orders over $2,000 | Prices so low we can't advertise! Add to cart for your savings!

HVACDIRECT.COM

Search entire store

SIZING GUIDE SIGN IN

1-888-976-9793 Today's Hours 8am - 11pm est

SHOPPING CART

Cooling | Heating | Ductless Mini Split | Commercial | Air Quality & Filters | Fans & Ventilation | Fireplaces & Outdoor | Water & Plumbing | Electrical & Solar | Parts & Tools

Home > 2 Ton 14.3 SEER2 Single Stage Air Conditioner Condenser - R32

2 Ton 14.3 SEER2 Single Stage Air Conditioner Condenser - R32

SAVE $498.00

By Private Brand Model AQ-GLXS4BA2410 ID 196469

SEE 77 REVIEWS | 5 QUESTIONS ANSWERED

In Stock - Ready to Ship

Was $2,370.00

Your Low Price $1,872.00

As low as $60.40/mo*

FREE SHIPPING

Tonnage: 1.5 Ton | 2 Ton | 2.5 Ton | 3 Ton | 3.5 Ton | 4 Ton | 5 Ton

SEER2 (Efficiency): 13.4 | 14.3 | 15.2

Limited Time: Extra 5% Off Private Brand Orders Over $1,400 — Use Code **FALLSALE** at Checkout!

Product Features

- ✓ Well-suited for small homes in various climates
- ✓ Shippable to Northern and Southern states
- ✓ Single stage condenser
- ✓ Pre-charged with R32 refrigerant

Line Sets: -- Please Select --

LSIK Install Kits: -- Please Select --

QTY 1 ADD TO CART

People also viewed:

26,913 Ratings | Goodman 2 Ton 13.4 SEER2 Central Air Conditioner Condenser - R32 Single | 2 Ton 13.4 SEER2 ACiQ Air Conditioner | Goodman 2 Ton 13.4 SEER2 Central Air Conditioner Condenser - R32 Single | Goodman 2 Ton 13.4 SEER2 Central Air Conditioner Condenser - R32 Single

Huge Sale on orders over $2,000 | Prices so low we can't advertise! Add to cart for your savings!

HVACDIRECT.COM

Search entire store

SIZING GUIDE SIGN IN

1-888-976-9793 Today's Hours 8am - 11pm est

SHOPPING CART

Cooling | Heating | Ductless Mini Split | Commercial | Air Quality & Filters | Fans & Ventilation | Fireplaces & Outdoor | Water & Plumbing | Electrical & Solar | Parts & Tools

Home > ACiQ 80% 60,000 BTU Single Stage Gas Furnace - 21" Width - Multi-Positional

ACiQ 80% 60,000 BTU Single Stage Gas Furnace - 21" Width - Multi-Positional

SAVE $328.00

By ACiQ Model N80MSN0702116A ID 46392

★★★★★ SEE 113 REVIEWS | FAQ 5 QUESTIONS ANSWERED

In Stock - 41 Ready to Ship

Was $1,639.00

Your Low Price $1,311.00

As low as $42.30/mo*

FREE SHIPPING

Heating BTU's: 40,000 BTU's | 60,000 BTU's | 80,000 BTU's | 100,000 BTU's | 120,000 BTU's | 140,000 BTU's | 150,000 BTU's

Cabinet Width: 14" | 17.5" | 21"

Furnace Efficiency / AFUE: 80%

Product Features

- ✓ Standard efficiency 80% furnace
- ✓ Single stage burner
- ✓ 18-speed constant torque ECM blower motor
- ✓ Can be installed in upflow, downflow, or horizontal applications
- ✓ Well-suited for small to medium-size homes in various climates
- ✓ 21" cabinet width

Wall-Mounted Thermostats

-- Please Select --

Install Accessories

- Propane Conversion Kit (AGAGCBNPS01A) + $173.00
- Return Air Package - 16.5" x 25" (811) + $319.00
- Knockdown Supply Plenum - 21" Width (80G36H) + $171.00

QTY 1 ADD TO CART

26,913 Ratings

NEW! TurboTrack Get by 4PM Today | Free shipping on orders over $99 • Your Zip: 76248

ORDER STATUS | SAVED CARTS | LISTS

SupplyHouse

Search for a product, brand, or SKU...

CONTACT & SUPPORT • Live Chat: Online Now

SIGN IN | CART

Plumbing | Heating | HVAC | Electrical | PEX | Pipe | Fittings | Valves | Tools | Resources | Our Team

TRADEMASTER PROGRAM FOR THE PROS

ARE YOU A PRO? Join for FREE! Free Shipping | Lower Prices | Free Returns | APPLY NOW

Hover image to zoom

Home > HVAC Supplies > Air Cleaners > Honeywell Home Electronic Air Cleaners

Electronic Air Cleaner, 16x20

Brand: Honeywell Home SKU: F300E1001 (133) Q&A: (25)

$766.90 each

ADD TO CART

In Stock Get 5 Tomorrow, Oct 3

FastTrack: Order by 4PM, receive tomorrow

TurboTrack: Order by 11AM, get by 4PM Today — Time Slots

Total Available: 24

MANUALS (3)

- Brochure
- Product Overview
- Submittal Sheet

This item replaces: F300A1620, FH8000A1620

Replacement Parts — View All

Free Shipping This item ships free

Easy Returns No restocking fee for 90 days

Product Highlights

- 16" x 20"
- 120v
- 1200 CFM
- 10 Year Warranty
- Duct

SupplyHouse.com

Search for a product, brand, or SKU...

CONTACT & SUPPORT
Live Chat: Online Now

SIGN IN | CART

Plumbing | Heating | HVAC | Electrical | PEX | Pipe | Fittings | Valves | Tools | Resources | Our Team

TRADEMASTER
PROGRAM FOR THE PROS
ARE YOU A PRO? Join for FREE!
Free Shipping | Lower Prices | Free Returns
APPLY NOW
Just takes 3 minutes!

Hover image to zoom

Home > Plumbing Supplies > Tools > Soldering Supplies > Brazing Rods

Stay-Silv 15% Flat Brazing Rods (28 Sticks per Tube)

Brand: Harris SKU: 15620F1 (10) Q&A: (0)

$132.37 each

ADD TO CART

In Stock Get 366 Mon, Dec 23

FastTrack
Order by 5PM, receive Monday
Details

TurboTrack
Order today, get by 12PM Monday
Time Slots

Free Shipping This item ships free
Easy Returns No restocking fee for 90 days

Product Highlights

15% Silver, 5% Phosphorus, 80% Copper

1 lb

Description

SupplyHouse.com

Search for a product, brand, or SKU...

CONTACT & SUPPORT
Live Chat: Online Now

SIGN IN | CART

Plumbing | Heating | HVAC | Electrical | PEX | Pipe | Fittings | Valves | Tools | Resources | Our Team

TRADEMASTER
PROGRAM FOR THE PROS
ARE YOU A PRO? Join for FREE!
Free Shipping | Lower Prices | Free Returns
APPLY NOW
Just takes 3 minutes!

Hover image to zoom

Home > HVAC Supplies > HVAC Replacement Parts > Lennox Parts > Lennox Filters

R410a Bi-flow Drier, 49W23

Brand: Lennox SKU: 49W23 (0) Q&A: (0)

$83.36 each

ADD TO CART

In Stock Get 2 Wed, Jul 17

Will this part work with my unit?
Click to see if this part is compatible with your unit.

Free Shipping On orders over $99
Easy Returns No restocking fee for 90 days

Description

49W23 is an official OEM R410a Bi-flow Drier for Lennox HVAC equipment.

Contact

Question? Call or text 888-757-4774

AMERICAN Copper & Brass, LLC Since 1986

All categories | What are you looking for?

800.624.8296 | LOGIN

QUICK ORDER | LAST CHANCE DEALS | LATEST BULK DISCOUNTS | PRODUCT CATEGORIES | BRANDS | CUSTOMER SERVICE | CONTACT

Home > 3/4" Type L Copper Pipe - 60' Soft Copper Coil

3/4" TYPE L COPPER PIPE - 60' SOFT COPPER COIL

SKU 34L60

$347.95

4 interest-free installments, or from **$31.41**/mo with shop Pay Check your purchasing power

by CAMBRIDGE-LEE IND LLC

Availability: Only 1 left!

Vendor: CAMBRIDGE-LEE IND LLC| **Vendor #** 320524 Cambridge-Lee 60' soft coil of 3/4" type L copper pipe. **Product Type**: Water Tube Type L **Applications**: Domestic Water Service, Fire Protection, Solar, Fuel Oil, HVAC, Natural Gas **Temper**: Soft **Length**: 60' Coil **Color Code**: Blue **Specification**: C12200, ASTM B-88 **SSID:** 80133

Quantity

− 1 + ADD TO CART

Inventory Blowout
Once it's gone, it's gone!

BUDGET
HEATING & AIR CONDITIONING INC.
WWW.BUDGETHEATING.COM

QUOTE | CART (0) | LOG IN | HELP

813-885-7999

Search here by model, brand or keyword...

EAL OF THE DAYMY ACCOUNT / ORDER STATUSCUSTOMER REFERRAL PROGRAM $75 OR $50HABLAMOS ESPAÑOLQUICK EDUCATIONCUSTOMER REVIEWSVIDEO TESTIMONIALSEMAIL USSEER2 INFORMAT

- REBATE CENTER
- SCRATCH, DENT, OR CLOSE OUT SPECIALS
- COMPLETE SPLIT SYSTEMS (INDOOR/OUTDOOR)
- MINI SPLIT DUCTLESS SYSTEMS WITH REMOTE
- PACKAGE / MOBILE HOME / ROOFTOP UNIT
- BARD WALL HUNG PACKAGE UNIT
- COMMERCIAL

Home > Copper Lines & Fittings >

Copper Fittings Kit 1 3/8 & 5/8

Larger Photo | Email A Friend

Like 0 | Share

List Price: $180.00
Our Price: $155.00
You save $25.00!

Starting at $14/mo with affirm.
See if you qualify

Availability: Usually Ships in 2 to 3 Business Days
Product Code: 37128

Qty: 1

Add To Cart

Add To Wishlist

SHOP BY BRAND | SHOP BY CATEGORY | WHO WE ARE | RESOURCE CENTER | TECHTOWN | TRACK MY ORDER | SAME DAY DELIVERY

HVAC Parts Are Here! Shop the top brands in the industry.

Take Parts Town on the Go! Download the industry's #1 app today!

Partpredictor **Find the parts you need to fix equipment!** Based on data from techs, powered by AI!

Home / Lennox / Condensate Drain Trap Kit, 1", PVC

Partspin®

Real OEM Part

Lennox 22H54 Condensate Drain Trap Kit, 1", PVC

List Price: **$ 103.45**

Quantity Available:	1
Manufacturer:	Lennox
Manufacturer #:	22H54
Parts Town #:	LEN22H54
Units:	Each
Fits Models:	View Models List
California Residents:	Proposition 65 Warning

Ship It!

In Stock

Ships from Parts Town

My Price: $ 77.59

1 more purchase options for shipping

1 +

Log in to enable Quick Order

ADD TO CART

ADD TO MY PARTS

Share this Part

Help us improve by sharing your feedback.

BUY COMFORT DIRECT.COM

Search the store | Search

My Account Sign In | Shopping Cart 0 Items

ALL CATEGORIES | About Us | Contact Us | Shipping & Returns | Size Your Equipment | Blog

- Clearance
- Weatherking By Rheem
- MRCOOL
- Westinghouse
- HVAC Supplies
- HVAC Material
- HVAC Parts
- Plumbing
- Tools
- Merchandise

MRCOOL COMFORT MADE SIMPLE

Home / HVAC Material / Ducting and Ventilation / Plenums and Filter Racks / 1410 Aprilaire Plenum (16 in. x 25 in.)

1410 Aprilaire Plenum (16 In. X 25 In.)

~~$210.46~~ $128.38

(You save $82.08)

No reviews yet | Write a Review

Brand:	Aprilaire
SKU:	AAPLEN1410
Condition:	New

4 interest-free payments or as low as $12/mo with affirm. See if you qualify

Quantity: − 1 +

Add To Cart | Add To My Wish List

Master Flow 14 in. x 20 in. to 14 in. Square to Round Transition

Size: 14 in. X 20 in /...

- Made from galvanized steel
- Half inch flange
- Install with sheet metal screws (not included)
- Always seal and insulate ductwork for greater system efficiency and comfort

Buying options

About these results

$100.10
+$8.26 est. tax
Free delivery
90-day returns
Home Depot
Top Quality Store · 4.5/5 ★ (1.8K)
PayPal accepted
Visit site

$125.10
+$10.32 est. tax
Free delivery
Free 30-day returns
eBay - luckyluciano711
PayPal, Google Pay accepted
Visit site
Buy now

Typical prices across the web

$100.10 at Home Depot

Low $100.10 $125.10 High

Report a listing

Product details

Used as a transition from air handler unit to air supply duct run. Connect to Round Duct Pipe or Flexible Ductwork. Flange allows user to secure unit to flat surface.

theacoutlet
(888) 474 - 9966

Daikin 5 Ton 14 Seer Commercial Heat Pump (208/230V)
Model: DZ14SA0603A

$3,305.00
Starting at $207/mo or 0% APR with affirm.
QTY: 1 ADD TO CART

ACCESSORIES | DESCRIPTION | SPECIFICATIONS | DOCUMENTS | CUSTOMER REVIEWS

Anti-Vibration Rubber Pads
Model: ISO-2
$24.95
QTY: 1 ADD TO CART

Flexible Electric Supply Whip (1/2 in x 6 ft)
Model: 84136
$34.95
QTY: 1 ADD TO CART

Flexible Electric Supply Whip (3/4 in x 6 ft)
Model: 84138
$46.95
QTY: 1 ADD TO CART

ProStat Non-Programmable Thermostat (1H/1C)
Model: PRS3110
$64.95
QTY: 1 ADD TO CART

SupplyHouse.com

Search for a product, brand, or SKU...

CONTACT & SUPPORT
Live Chat: Online Now

SIGN IN | CART

Plumbing | Heating | HVAC | Electrical | PEX | Pipe | Fittings | Valves | Tools | Resources | Our Team

Hover image to zoom

Home > Heating Supplies & Parts > Thermostats > Honeywell Thermostats > T Pro Series

T4 Pro Programmable Thermostat, 1H/1C Heat Pump, 1H/1C Conventional

Brand: Honeywell Home SKU: TH4110U2005 (53) Q&A: (1)

$53.57 each

ADD TO CART

In Stock Get 239 Tue, May 21

FastTrack
Order today, receive Tuesday
Details

TurboTrack
Order today, get by 12PM Tomorrow
Time Slots

MANUALS (1)
Brochure

Free Shipping On orders over $99
Easy Returns No restocking fee for 90 days

Product Highlights

- 7 Day, Programmable, 5-1-1 Day, 5-2 Day
- 24v
- 1 Heat/1 Cool
- Square
- Hardwired, Battery
- White

Best Seller | Memorial Day

658

Halex

60 Amp Non-Fusible Metallic AC Disconnect

(228) Questions & Answers (29)

Hover Image to Zoom

$12.98

- Use with air conditioner units; heat pumps; spas; hot tubs
- Non-fused pullout indicates on/off position
- Padlockable
- View More Details

Pickup at Keiler | Delivering to 76248

Pickup
Today
9 in stock
FREE

Delivery
Thursday, May 23
202 available
FREE

Get it as soon as today. Schedule your delivery in checkout.

- 1 + Add to Cart

Free & Easy Returns In Store or Online
Return this item within 90 days of purchase. Read Return Policy

Live Chat | Feedback

Back to search

Zillow

Save Share More

Off market

Zestimate®

$212,400

607 Westchester Dr, Wexford, PA 15090

2 beds **1** baths **1,088** sqft

Claim home

Est. refi payment: $1,148/mo Refinance your loan

Townhouse	Built in 1981	1,088 Square Feet Lot
$212,400 Zestimate®	$195/sqft	$1,525 Estimated rent