Eaton Corporation
Electrical Engineering Services & Systems
488 Madison Avenue
New York, NY 10022

August 14, 2025

Subject: **Project Name:** **Regeneron 3-SUB 10MVA XFMR Radiator Repairs**
Eaton Proposal#: NA04-250730-02-BM-Rev1

Thank you for considering Eaton's Electrical Engineering Services & Systems (EESS) for your electrical solutions requirements. This document details our proposed scope of work at Regeneron in Tarrytown.

1. SCOPE OF WORK

Eaton Corporation will provide the necessary field service personnel, tools, materials, and approved test equipment to repair the damaged radiator on one (1) Cooper Power Transformer sold on Eaton GO# MNY0011335, serial No. 2359000998.

NOTE: Proposal excludes all rigging services. A list of excluded tasks is provided for Bay Crane use in estimating their portion of the work. Proposal assumes the transformer is not connected electrically requiring no outages, stand-by power, etc.

Engineering / Project Management:

- Assign a Project Manager (PM) with overall responsibility for the initiation, planning & scheduling, execution, monitoring, controlling and closure of the project.
- Assign a lead field engineer responsible for all field personnel, site safety, quality, and daily communication with site personnel.
- Perform project kick-off meeting.

Labor:

- Mobilize:
  - Provide, deliver, and stage all test equipment, tools, and materials.
  - Conduct Site safety review.
- Removal:
  - Perform as-found electrical testing to include oil sample analysis in accordance with the Eaton Site Acceptance Testing work-scope.
  - Provide and install spill containment.
  - Close radiator valves and remove radiator oil to 55Gal drum.
  - Disconnect and remove the radiator. All rigging by Bay Crane supported by EESS personnel.
  - Radiator to be removed from the project site and disposed by Bay Crane.
- Installation:
  - Ship replacement radiator to Bay Crane.
  - Install replacement radiator. All rigging by Bay Crane supported by EESS personnel.
  - Open radiator valves to fill radiator. Top off transformer with new FR3 oil. Oil to be filtered while filling.
  - Pull vacuum and top off nitrogen blanket.
  - Perform as-left electrical testing to include oil sample analysis in accordance with the Eaton Site Acceptance Testing work-scope.

- De-Mobilize:
  - Assist client with energizing equipment.
  - Remove Eaton applied LOTO and grounds.
  - Clean work area and depart work site.
  - Dispose oil.

Materials:
(2) Cooper Power Systems 22-Pan Demount 20.5W Radiator
(2) 55gal drum, FR3 Transformer oil

2. COMPLETION

Upon completion of the project, Eaton will provide:
- Engineering report including findings, test data, and recommendations.
- All applicable Federal / State / Local environmental documentation for disposed oil.

3. PRICING

All services as detailed within this proposal: $138,209.41

4. DELIVERY

- The scheduling of work will be mutually agreed upon between the customer and Eaton's Electrical Engineering Services & Systems.
- Please allow 3 weeks for scheduling onsite services.
- Replacement radiator – expedited production lead-time: 8 weeks

5. QUALIFICATIONS / CLARIFICATIONS

- All work to be performed during the purchased time classification.
- Proposal includes 30 minutes of customer site and/or safety training for the first workday. Additional safety training, drug testing, background checks or other site-specific requirements beyond what is included will be treated as additional work as detailed below.
- Additional work or materials beyond the scope of this proposal will be quoted with a firm-fixed proposal. Written authorization will be required prior to execution of additional work.
- Reschedule, Cancellation and Delay Charges: If a job is cancelled, delayed, rescheduled, or postponed 5 days or less prior to scheduled service, Eaton reserves the right to assess a charge of 35% of the purchase order value or actual costs, plus a 15% handling charge (whichever is greater).
- Method of procedure (MOP) development or meeting time not outlined in the scope of work will be treated as an extra.

Eaton Proprietary and Confidential
Unauthorized Use and/or Disclosure is Strictly Prohibited

6. CUSTOMER RESPONSIBILITIES

- Ensure that all equipment is available upon arrival of Eaton personnel, including removal from service to permit continuous progression of work.
- Identify site contact for this project.
- Supply a suitable and stable source of power for operation of test and motorized equipment at each test site when normal power is removed.
- Provide a place to receive and unload materials, equipment, or other supplies.
- Perform all rigging services required to remove the existing radiator and install the new. This includes:
    - Provide licensed personnel and suitably rated equipment to remove the radiator from the transformer. Unit weighs approximately 1056lbs.
    - Dispose the removed radiator. Provide any environmental documentation to the customer as required.
    - Receive the replacement radiator at Bay Crane yard.
    - Deliver the replacement radiator to the project site.
    - Provide licensed personnel and suitably rated equipment to install the radiator on the transformer. Unit weighs approximately 1056lbs.

7. SAFETY TRAINING OF EATON FIELD PERSONNEL:

All Eaton field personnel received training to comply with OSHA CFR1910 Electrical Safety Standard, which sets minimum safety rules and practices for the design, operation, and maintenance of high-voltage systems (over 600 volts). Safety standards are in place to meet or exceed NFPA 70E requirements, and appropriate Personal Protective Equipment (PPE) have been issued. The customer is responsible to ensure that any supporting plant personnel have also be fully trained in electrical safety and provided with the appropriate PPE.

8. SAFETY ARC-FLASH PROVISIONAL STATEMENT:

The customer supplied Arc-Flash study along with their labeled equipment to meet NFPA requirements will be used to determine the Personal Protective Equipment (PPE) required to perform the work required for this proposal. When a current study and labeling is not available, the time required to determine the proper PPE will be at the current rate per hour, unless included within the Eaton scope of work. Eaton will not perform work activities in situations where the proper level of PPE is not practical. At no time will work be performed when the arc-flash exposure levels are above 40cal/cm^2.

9. PROPRIETARY AND CONFIDENTIAL INFORMATION

This submittal contains Eaton proprietary and confidential information, which may only be used by The Eaton Customer to evaluate and respond to this submittal. By accepting this submittal from Eaton, The Eaton Customer agrees to not use this submittal, or any information contained herein, in any manner adverse to Eaton's interests; to keep in confidence the submittal and all information contained; and to not disclose to any third party or publish this submittal, any portion thereof, or any information contained herein without Eaton's prior written consent.

10. ORDER ENTRY

Please email an electronic copy of the purchase order to JoeAStellato@Eaton.com. To ensure proper order processing, please include the following information in the PO:

- Addressed to: Eaton Corporation
  488 Madison Avenue
  New York, NY 10022
- The Eaton proposal number as listed on page 1.
- The ship-to address and site contact name, number, and email.
- The bill-to address and purchasing contact information.

11. TERMS AND CONDITIONS

- Any order arising out of this offer will be governed by the conditions contained in Eaton Selling Policy 25-000 dated September 1, 2021 (attached).
- Quoted prices are valid for thirty (30) days.
- The prices quoted in this proposal exclude any applicable taxes and potential additional tariffs beyond the proposal date. Any subsequent tariff-related price adjustments will be passed on to the Buyer.
- This proposal, as presented, is not subject to prevailing wage requirements. In the event that the project necessitates the payment of prevailing wages by the contractor and all subcontractors, including Eaton, for work performed under this proposal, Eaton reserves the right to amend the pricing to ensure compliance with prevailing wage statutes.
- Material shipment via LTL, FOB factory pre-paid and allowed. Unless specified within this proposal, special trucking such as union driver, flatbed truck, lift-gate, etc. is not included.
- Third party billing will be subject to an additional 15% fee.
- Eaton reserves the right to invoice based on progressive work-scope and material delivery or, where detailed in this proposal, according to the progress payment schedule.
- A Memorandum of Insurance (MOI) detailing Eaton's standard insurance coverage will be provided upon request. A certificate of Insurance (COI) naming specific parties is not included in this offering.

It is a privilege to have this opportunity to be of service. If there are any further questions or needs, please do not hesitate to contact me. Eaton's Electrical Engineering Services & Systems looks forward to working with you on this project.

Eaton Proprietary and Confidential
Unauthorized Use and/or Disclosure is Strictly Prohibited